# SECTION EXHAUST SYSTEM C

D

Ε

Н

J

Κ

L

Μ

# CONTENTS

| PREPARATION              | 2 |
|--------------------------|---|
| Special Service Tool     | 2 |
| Commercial Service Tools | 2 |
| EXHAUST SYSTEM           | 3 |

| Checking Exhaust System3      | F |
|-------------------------------|---|
| Removal and Installation      |   |
| REMOVAL4                      |   |
| INSTALLATION4                 | G |
| INSPECTION AFTER INSTALLATION | 0 |

# PREPARATION

# PREPARATION

PFP:00002

EBS00QUH

EBS00QUI

# **Special Service Tool**

The actual shapes of Kent-Moore tools may differ from those of special service tools illustrated here.

| Tool number<br>(Kent-Moore No.)<br>Tool name           |  | Description   |
|--|--|---|
| KV10114400<br>(J-38365)<br>Heated oxygen sensor wrench | a<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0<br>0 | Loosening or tightening heated oxygen sen-<br>sors:<br>a: 22 mm (0.87 in) |

# **Commercial Service Tools**

| (Kent-Moore No.)<br>Tool name   |           | Description  |
|---|-----------|--|
| (J-43897-18)<br>(J-43897-12)<br>Oxygen sensor thread cleaner                                    | AEM488    | Reconditioning the exhaust system threads<br>before installing a new heated oxygen sensor<br>(Use with anti-seize lubricant shown below):<br>a: J-43897-18 (18 mm, 0.71 in) dia. for zirco-<br>nia oxygen sensor<br>b: J-43897-12 (12 mm, 0.47 in) dia. for tita-<br>nia oxygen sensor |
| Anti-seize lubricant (Permatex 133AR<br>or equivalent meeting MIL specifica-<br>tion MIL-A-907) | AEM489    | Lubricating oxygen sensor thread cleaning<br>tool when reconditioning exhaust system<br>threads  |
| Power tool  |           | Loosening nuts and bolts   |
|   | PBIC0190E |  |


# EXHAUST SYSTEM

# EXHAUST SYSTEM

### **Checking Exhaust System**

Check exhaust pipes, muffler and mounting for improper attachment, leaks, cracks, damage or deterioration.

If anything is found, repair or replace damaged parts.




PFP:20100

FBS00QUJ

EBS00QUK

А

### **Removal and Installation**



← Front

### **CAUTION:**

- Be sure to use genuine exhaust system parts or equivalents which are specially designed for heat resistance, corrosion resistance, and shape.
- Perform the operation with the exhaust system fully cooled. The system will be hot just after the
  engine stops.
- Be careful not to cut your hand on the heat insulator edge.

### REMOVAL

Remove exhaust system components using power tool.

### INSTALLATION

Installation is in the reverse order of removal.

### **CAUTION:**

- Always replace exhaust gaskets with new ones when reassembling.
- Before installing a new heated oxygen sensor, clean and lube the exhaust tube threads using tool.

**Tool number** 

A : — (J-43897-18)

B : — (J-43897-12)

- Discard any heated oxygen sensor which has been dropped from a height of more than 0.5 m (19.7 in) onto a hard surface such as a concrete floor; install a new one.
- Do not over-torque the heated oxygen sensor. Doing so may damage the heated oxygen sensor, resulting in the MIL coming on.
- If any mounting insulator is badly deformed, repair or replace it. If deposits such as mud pile up on the mounting insulators, clean and inspect them.
- Temporarily tighten the mounting nuts on the exhaust manifold side and the mounting bolts on the vehicle side. Check each part for interference with other components, and then tighten the nuts and bolts to specification.

### **INSPECTION AFTER INSTALLATION**

- With the engine running, check exhaust tube joints for gas leakage and unusual noises.
- Check to ensure that mounting brackets and mounting rubbers are installed properly and free from undue stress. Improper installation could result in excessive noise and vibration.