BODY EXTERIOR, DOORS, ROOF & VEHICLE SECURITY

CONTENTS

| PRECAUTION |
|--|
| PRECAUTIONS |
| Precaution for Procedure without Cowl Top Cover3 Precautions for Removing Battery Terminal |
| PREPARATION5 |
| PREPARATION 5 Special Service Tools 5 Commercial Service Tools 5 |
| SYMPTOM DIAGNOSIS6 |
| SQUEAK AND RATTLE TROUBLE DIAG- NOSES |
| REMOVAL AND INSTALLATION12 |
| FRONT BUMPER12Exploded View12Removal and Installation13 |
| REAR BUMPER17Exploded View17Removal and Installation18 |
| FRONT GRILLE |
| COWL TOP22Exploded View22Removal and Installation22 |
| FENDER PROTECTOR24 |

| FENDER PROTECTOR 24 FENDER PROTECTOR : Exploded View 24 FENDER PROTECTOR : Removal and Installa- tion 24 | F |
|---|--------|
| REAR WHEEL HOUSE PROTECTOR24REAR WHEEL HOUSE PROTECTOR : ExplodedView | Н |
| FLOOR SIDE FAIRING 26 Exploded View 26 Removal and Installation 26 | l J |
| OVER FENDER | EXT |
| ROOF RAIL30Exploded View30Removal and Installation30 | L |
| ROOF SIDE MOLDING 32 Exploded View 32 Removal and Installation 32 | M |
| DOOR OUTSIDE MOLDING33Exploded View33Removal and Installation33 | Ν |
| DOOR PARTING SEAL35Exploded View | 0 |
| SILL MOLDING | Ρ |
| DOOR SASH COVER38Exploded View38Removal and Installation38 | |

SECTION EXT

А

В

D

Е

EXTERIOR c

| 2 |
|---------|
| 2 |
| 2 |
| ļ - |
| |

| Removal and Installation | |
|--------------------------|----|
| BACK DOOR FINISHER | 45 |
| Exploded View | |
| Removal and Installation | |
| SIDE STEP | 46 |
| Exploded View | |
| Removal and Installation | |

PRECAUTIONS

< PRECAUTION > PRECAUTION

| PRECAUTIONS | A |
|--|---|
| FRECAUTIONS | |
| Precaution for Supplemental Restraint System (SRS) "AIR BAG" and "SEAT BELT | В |
| PRE-TENSIONER" | |
| The Supplemental Restraint System such as "AIR BAG" and "SEAT BELT PRE-TENSIONER", used along with a front seat belt, helps to reduce the risk or severity of injury to the driver and front passenger for certain types of collision. Information necessary to service the system safely is included in the "SRS AIR BAG" and "SEAT BELT" of this Service Manual. | С |
| WARNING: Always observe the following items for preventing accidental activation. • To avoid rendering the SRS inoperative, which could increase the risk of personal injury or death in | D |

- the risk of personal injury the event of a collision that would result in air bag inflation, all maintenance must be performed by an authorized NISSAN/INFINITI dealer.
- Improper maintenance, including incorrect removal and installation of the SRS, can lead to personal injury caused by unintentional activation of the system. For removal of Spiral Cable and Air Bag Module, see "SRS AIR BAG".
- Never use electrical test equipment on any circuit related to the SRS unless instructed to in this Service Manual. SRS wiring harnesses can be identified by yellow and/or orange harnesses or harness connectors.

PRECAUTIONS WHEN USING POWER TOOLS (AIR OR ELECTRIC) AND HAMMERS


WARNING:

Always observe the following items for preventing accidental activation.

- When working near the Air Bag Diagnosis Sensor Unit or other Air Bag System sensors with the ignition ON or engine running, never use air or electric power tools or strike near the sensor(s) with a hammer. Heavy vibration could activate the sensor(s) and deploy the air bag(s), possibly causing serious injury.
- When using air or electric power tools or hammers, always switch the ignition OFF, disconnect the battery, and wait at least 3 minutes before performing any service.

Precaution for Procedure without Cowl Top Cover

When performing the procedure after removing cowl top cover, cover the lower end of windshield with urethane, etc to prevent damage to windshield.



Precautions for Removing Battery Terminal

When removing the 12V battery terminal, turn OFF the ignition • switch and wait at least 30 seconds. NOTE:

ECU may be active for several tens of seconds after the ignition switch is turned OFF. If the battery terminal is removed before ECU stops, then a DTC detection error or ECU data corruption may occur.

 For vehicles with the 2-batteries, be sure to connect the main battery and the sub battery before turning ON the ignition switch. NOTE:

f]0 BATTERY SEF289H

INFOID:0000000010257779

INFOID:000000010257777



Е

Н

PRECAUTIONS

< PRECAUTION >

If the ignition switch is turned ON with any one of the terminals of main battery and sub battery disconnected, then DTC may be detected.

• After installing the 12V battery, always check "Self Diagnosis Result" of all ECUs and erase DTC. NOTE:

The removal of 12V battery may cause a DTC detection error.

Precaution for Work

- After removing and installing the opening/closing parts, be sure to carry out fitting adjustments to check their operation.
- Check the lubrication level, damage, and wear of each part. If necessary, grease or replace it.

PREPARATION

< PREPARATION > PREPARATION PREPARATION

Special Service Tools

The actual shapes of Kent-Moore tools may differ from those of special service tools illustrated here.

| Tool number (Kent-Moore No.) Tool name | | Description | |
|--|-----------|----------------------------|--|
| (J-39570) Chassis ear | SIIA0993E | Locates the noise | |
| (J-50397) NISSAN Squeak and Rat- tle Kit | SIIA0994E | Repairs the cause of noise | |

Commercial Service Tools

INFOID:0000000010257782

А


В

| | Tool name | Description | J |
|--------------|-----------------------|--------------------------------------|-----|
| Engine ear | SIIA0995E | Locates the noise | EXT |
| Remover tool | JAG JAJ JAKA3050ZZ | Removes clips, pawls and metal clips | M |
| Power tool | | Loosening bolts, nuts and screws | P |
| | PIIB1407E | | |

< SYMPTOM DIAGNOSIS >

SYMPTOM DIAGNOSIS SQUEAK AND RATTLE TROUBLE DIAGNOSES

Work Flow



CUSTOMER INTERVIEW

Interview the customer if possible, to determine the conditions that exist when the noise occurs. Use the Diagnostic Worksheet during the interview to document the facts and conditions when the noise occurs and any customer comments. Refer to <u>EXT-10</u>, "Diagnostic Worksheet". This information is necessary to duplicate the conditions that exist when the noise occurs.

- The customer may not be able to provide a detailed description or the location of the noise. Attempt to obtain all the facts and conditions that exist when the noise occurs (or does not occur).
- If there is more than one noise in the vehicle, perform a diagnosis and repair the noise that the customer is concerned about. This can be accomplished by performing a test drive with the customer.
- After identifying the type of noise, isolate the noise in terms of its characteristics. The noise characteristics are provided so that the customer, service adviser, and technician use the same language when describing the noise.
- Squeak (Like tennis shoes on a clean floor)
 Squeak characteristics include the light contact / fast movement / brought on by road conditions / hard surfaces = high-pitched noise / softer surfaces = low-pitched noises / edge to surface = chirping
- Creak (Like walking on an old wooden floor)
 Creak characteristics include firm contact / slow movement/twisting with a rotational movement / pitch dependent on materials / often brought on by activity.
- Rattle (Like shaking a baby rattle) Rattle characteristics include fast repeated contact / vibration or similar movement / loose parts/missing clip or fastener / incorrect clearance.
- Knock (Like a knock on a door) Knock characteristics include hollow sounds / sometimes repeating / often brought on by driver action.
- Tick (Like a clock second hand) Tick characteristics include gentle contacting of light materials / loose components / can be caused by driver action or road conditions.
- Thump (Heavy, muffled knock noise) Thump characteristics include softer knock / dull sounds often brought on by activity.
- Buzz (Like a bumblebee) Buzz characteristics include high frequency rattle / firm contact.
- Often the degree of acceptable noise level varies depending upon the person. A noise that a technician may judge as acceptable may be very irritating to a customer.
- Weather conditions, especially humidity and temperature, may have a great effect on noise level.

DUPLICATE THE NOISE AND TEST DRIVE

< SYMPTOM DIAGNOSIS >

| If possible, drive the vehicle with the customer until the noise is duplicated. Note any additional information on the Diagnostic Worksheet regarding the conditions or location of the noise. This information can be used to duplicate the same conditions when the repair is reconfirmed. If the noise can be duplicated easily during the test drive, to help identify the source of the noise, try to duplicate the noise with the vehicle stopped by doing one or all of the following items: 1) Close a door. | А |
|--|----|
| 2) Tap or push/pull around the area where the noise appears to be coming from. 3) Rev the engine. 4) Use a floor jack to recreate vehicle "twist". | С |
| 5) At idle, apply engine load (electrical load, half-clutch on M/T models, drive position on A/T models). 6) Raise the vehicle on a hoist and hit a tire with a rubber hammer. Drive the vehicle and attempt to duplicate the conditions the customer states exist when the noise occurs. If it is difficult to duplicate the noise, drive the vehicle slowly on an undulating or rough road to stress the | D |
| vehicle body. CHECK RELATED SERVICE BULLETINS After verifying the customer concern or symptom, check ASIST for Technical Service Bulletins (TSBs) related | E |
| to the concern or symptom. If a TSB relates to the symptom, follow the procedure to repair the noise. | |
| LOCATE THE NOISE AND IDENTIFY THE ROOT CAUSE | F |
| Narrow down the noise to a general area. To help pinpoint the source of the noise, use a listening tool (Chassis ear: J-39570, engine ear, and mechanics stethoscope). | G |
| 2. Narrow down the noise to a more specific area and identify the cause of the noise by: | |
| Removing the component(s) in the area that is / are suspected to be the cause of the noise. Do not use too much force when removing clips and fasteners, otherwise clips and fasteners can be broken or lost during the repair, resulting in the creation of new noise. | Н |
| Tapping or pushing/pulling the component(s) that is / are suspected to be the cause of the noise. Do not tap or push/pull the component(s) with excessive force, otherwise the noise is eliminated only temporarily. | 1 |
| Feeling for a vibration by hand by touching the component(s) that is / are suspected to be the cause of the noise. | |
| Placing a piece of paper between components that are suspected to be the cause of the noise. Looking for loose components and contact marks. Refer to <u>EXT-8, "Inspection Procedure"</u>. | J |
| REPAIR THE CAUSE | EX |
| If the cause is a loose component, tighten the component securely. | |
| If the cause is insufficient clearance between components: Separate components by repositioning or loosening and retightening the components, if possible. Insulate components with a suitable insulator such as urethane pads, foam blocks, felt cloth tape, or ure- thane tape. A NISSAN Squeak and Rattle Kit (J-50397) is available through the authorized NISSAN Parts | |
| Department. CAUTION: | M |
| Never use excessive force as many components are constructed of plastic and may be damaged. NOTE: | |
| Always check with the Parts Department for the latest parts information. The following materials are contained in the NISSAN Squeak and Rattle Kit (J-50397) are listed on the inside cover of the kit; and can each be ordered separately as needed. | Ν |
| URETHANE PADS [1.5 mm (0.059 in) thick] | 0 |
| Insulates connectors, harness, etc. • 76268-9E005: $100 \times 135 \text{ mm} (3.937 \times 5.315 \text{ in})$ | |
| 76884-71L01: 60 × 85 mm (2.362 × 3.346 in) 76884-71L02: 15 × 25 mm (0.591 × 0.984 in) INSULATOR (Foam blocks) | Ρ |
| Insulates components from contact. Can be used to fill space behind a panel. | |
| 73982-9E000: 45 mm (1.772 in) thick, 50 × 50 mm (1.969 × 1.969 in) 73982-50Y00: 10 mm (0.394 in) thick, 50 × 50 mm (1.969 × 1.969 in) | |
| INSULATOR (Light foam block) 80845-71L00: 30 mm (1.181 in) thick, 30 \times 50 mm (1.181 \times 1.969in) | |
| FELT CLOTHTAPE | |

EXT-7

< SYMPTOM DIAGNOSIS >

Used to insulate where movement does not occur. Ideal for instrument panel applications.

• 68370-4B000: 15 imes 25 mm (0.591 imes 0.984 in) pad

• 68239-13E00: 5 mm (0.197 in) wide tape roll

The following materials, not found in the kit, can also be used to repair squeaks and rattles. UHMW (TEFLON) TAPE

Insulates where slight movement is present. Ideal for instrument panel applications. SILICONE GREASE Used in place of UHMW tape that is visible or does not fit. Only lasts a few months. SILICONE SPRAY Used when grease cannot be applied. DUCT TAPE Used to eliminate movement.

CONFIRM THE REPAIR

After repair is complete, test drive the vehicle to confirm that the cause of noise is repaired by test driving the vehicle. Operate the vehicle under the same conditions as when the noise originally occurred. Refer to the notes on the Diagnostic Worksheet.

Inspection Procedure

INFOID:000000010257784

Refer to Table of Contents for specific component removal and installation information.

INSTRUMENT PANEL

Most incidents are caused by contact and movement between:

- 1. The cluster lid A and instrument panel
- 2. Acrylic lens and combination meter housing
- 3. Instrument panel to front pillar garnish
- 4. Instrument panel to windshield
- 5. Instrument panel mounting pins
- 6. Wiring harnesses behind the combination meter
- 7. A/C defroster duct and duct joint

These incidents can usually be located by tapping or moving the components to duplicate the noise or by pressing on the components while driving to stop the noise. Most of these incidents can be repaired by applying felt cloth tape or silicon spray (in hard to reach areas). Urethane pads can be used to insulate wiring harness.

CAUTION:

Never use silicone spray to isolate a squeak or rattle. If the area is saturated with silicone, the recheck of repair becomes impossible.

CENTER CONSOLE

Components to check include:

- 1. Shifter assembly cover to finisher
- 2. A/C control unit and cluster lid C
- 3. Wiring harnesses behind audio and A/C control unit

The instrument panel repair and isolation procedures also apply to the center console.

DOORS

Check the following items:

- 1. Finisher and inner panel making a slapping noise
- 2. Inside handle escutcheon connection to door finisher
- 3. Wiring harnesses tapping
- 4. Door striker out of alignment causing a popping noise on starts and stops

Tapping, moving the components, or pressing on them while driving to duplicate the conditions can isolate many of these incidents. The areas can usually be insulated with felt cloth tape or insulator foam blocks from the NISSAN Squeak and Rattle Kit (J-50397) to repair the noise.

TRUNK

Trunk noises are often caused by a loose jack or loose items put into the trunk by the customer. In addition check for the following items:

Revision: 2014 October

EXT-8

< SYMPTOM DIAGNOSIS >

| 1. Trunk lid dumpers out of adjustment | - |
|--|--------|
| 2. Trunk lid striker out of adjustment | А |
| 3. Trunk lid torsion bars knocking together | |
| 4. A loose license plate or bracket | |
| Most of these incidents can be repaired by adjusting, securing, or insulating the item(s) or component(s) caus- | В |
| ing the noise. | |
| SUNROOF/HEADLINING | С |
| Noises in the sunroof / headlining area can often be traced to one of the following items: | 0 |
| 1. Sunroof lid, rail, linkage, or seals making a rattle or light knocking noise | |
| 2. Sunvisor shaft shaking in the holder | D |
| Front or rear windshield touching headlining and squeaking | |
| Again, pressing on the components to stop the noise while duplicating the conditions can isolate most of these incidents. Repairs usually consist of insulating with felt cloth tape. | e E |
| SEATS | |
| When isolating seat noise it is important to note the position the seat is in and the load placed on the seat when the noise occurs. These conditions should be duplicated when verifying and isolating the cause of the noise. | |
| Causes of seat noise include: | |
| 1. Headrest rods and holder | G |
| 2. A squeak between the seat pad cushion and frame | |
| 3. The rear seatback lock and bracket | |
| These noises can be isolated by moving or pressing on the suspected components while duplicating the con- ditions under which the noise occurs. Most of these incidents can be repaired by repositioning the component or applying urethane tape to the contact area. | |
| UNDERHOOD | |
| Some interior noise may be caused by components under the hood or on the engine wall. The noise is then | 1 |
| transmitted into the passenger compartment. Causes of transmitted underhood noise include: | J |
| 1. Any component mounted to the engine wall | |
| 2. Components that pass through the engine wall | EVT |
| 3. Engine wall mounts and connectors | EXT |
| 4. Loose radiator mounting pins | |
| 5. Hood bumpers out of adjustment | L |
| 6. Hood striker out of adjustment | |
| These noises can be difficult to isolate since they cannot be reached from the interior of the vehicle. The best method is to secure, move, or insulate one component at a time and test drive the vehicle. Also, engine RPM or load can be changed to isolate the noise. Repairs can usually be made by moving, adjusting, securing, or insulating the component causing the noise. | M |
| | Ν |
| | 1 N |
| | |
| | 0 |
| | |

< SYMPTOM DIAGNOSIS >

Diagnostic Worksheet




SQUEAK & RATTLE DIAGNOSTIC WORKSHEET

Dear Infiniti Customer:

We are concerned about your satisfaction with your Infiniti vehicle. Repairing a squeak or rattle sometimes can be very difficult. To help us fix your Infiniti right the first time, please take a moment to note the area of the vehicle where the squeak or rattle occurs and under what conditions. You may be asked to take a test drive with a service consultant or technician to ensure we confirm the noise you are hearing.

I. WHERE DOES THE NOISE COME FROM? (circle the area of the vehicle)

The illustrations are for reference only, and may not reflect the actual configuration of your vehicle.




Continue to page 2 of the worksheet and briefly describe the location of the noise or rattle. In addition, please indicate the conditions which are present when the noise occurs.

< SYMPTOM DIAGNOSIS >

| , | noise occurs: | |
|--|--|--|
| | | |
| II. WHEN DOES IT OCCUR? (please | check the boxes that apply) | |
| anytime 1st time in the morning only when it is cold outside only when it is hot outside | after sitting out in the rain when it is raining or wet dry or dusty conditions other: | |
| III. WHEN DRIVING: | IV. WHAT TYPE OF NOISE | |
| ☐ through driveways☐ over rough roads☐ over speed bumps | squeak (like tennis shoes on a clean floor) creak (like walking on an old wooden floor) rattle (like shaking a baby rattle) | |
| only about mph on acceleration coming to a stop | knock (like a knock at the door) tick (like a clock second hand) thump (heavy, muffled knock noise) | |
| on turns: left, right or either (circle) | buzz (like a bumble bee) | |
| | | |
| which passengers of earge other: after driving miles or | minutes | |
| □ other: | HIP PERSONNEL | |
| other: miles or TO BE COMPLETED BY DEALERSH Test Drive Notes: | HIP PERSONNEL | |
| other: miles or after driving miles or TO BE COMPLETED BY DEALERSH | HIP PERSONNEL YES NO Initials of person performing Initials of person performing Initials of person performing | |
| Other: miles or TO BE COMPLETED BY DEALERSH Test Drive Notes: Vehicle test driven with customer Noise verified on test drive Noise source located and repaired | HIP PERSONNEL YES NO Initials of person performing Image: | |

REMOVAL AND INSTALLATION FRONT BUMPER

Exploded View



< REMOVAL AND INSTALLATION >


| 4 Duran en meldine kan skat hill | 0 | For some shares have been | 0 | Direct |
|--|--|---|-----------|-------------------------------------|
| Bumper molding bracket LH Bumper molding | 2. 5. | Energy absorber LH Grommet | 3. 6. | Rivet Bumper molding bracket RH |
| Bumper molding Energy absorber RH | 5. 8. | Bumper fascia assembly | 0. 9. | Front fog lamp finisher RH |
| 10. Front grille lower molding | 0. 11. | | 9. 12. | License plate bracket |
| 13. Front fog lamp finisher LH | 14. | Bumper retainer bracket LH | 15. | Bumper retainer |
| 16. Bumper side bracket LH | 17. | Grommet LH | 18. | |
| 19. Grommet RH | 20. | Bumper molding bracket RH | 21. | |
| 22. Bumper retainer bracket centre | 23. | Bumper molding bracket LH | 24. | |
| 25. Front combination lamp | | | | |
| A : Pawl | | | | |
| : Metal clip | | | | |
| Always replace after every disasse | embly | | | |
| • | | | | |
| O, igodot : Indicates that the part is connect | ed at poir | nts with same symbol in actual ve | nicle. | |
| Removal and Installation | | | | INFOID:000000010257787 |
| | | | | |
| EMOVAL | | | | |
| | | | | |
| | | nnly strong force to it a | | a construit to provent contact with |
| umper fascia is made of resin. | Never a | pply strong force to it, a | nd be | e careful to prevent contact with |
| umper fascia is made of resin. N il. | Never a | pply strong force to it, a | nd be | e careful to prevent contact with |
| Sumper fascia is made of resin. Noise il Fully open hood assembly. | | | nd be | e careful to prevent contact with |
| Bumper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX | | | nd be | e careful to prevent contact with |
| Bumper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. | <u>(T-20, "I</u> | Removal and Installation". | | e careful to prevent contact with |
| Bumper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. Remove front fender drip control in the second se | <u>(T-20, "f</u> over. Re | Removal and Installation". efer to DLK-228, "FRONT | | · |
| umper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to <u>EX</u> Remove bumper molding. Remove front fender drip contract lation". | <u>(T-20, "f</u> over. Re | Removal and Installation". efer to DLK-228, "FRONT | | · |
| Remove front grille. Refer to EX Remove bumper molding. Remove front fender drip or <u>Installation</u>". Remove bumper molding u RH). | <u>(T-20, "f</u> over. Re | Removal and Installation". efer to DLK-228, "FRONT | | · |
| iumper fascia is made of resin. No. ii. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. Remove front fender drip control in the second sec | <u>(T-20, "f</u> over. Re | Removal and Installation". efer to DLK-228, "FRONT | FENI | · |
| umper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. 1. Remove front fender drip constallation". 2. Remove bumper molding to RH). | <u>(T-20, "f</u> over. Re | Removal and Installation". efer to DLK-228, "FRONT | FENI | DER DRIP COVER : Removal and |
| umper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. 1. Remove front fender drip constallation". 2. Remove bumper molding to RH). | <u>(T-20, "f</u> over. Re | Removal and Installation". efer to DLK-228, "FRONT | FENI | DER DRIP COVER : Removal and |
| umper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. Remove front fender drip control (Installation"). Remove bumper molding to RH). | <u>(T-20, "f</u> over. Re | Removal and Installation". efer to DLK-228, "FRONT | FENI | DER DRIP COVER : Removal and |
| umper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. Remove front fender drip control (Installation"). Remove bumper molding to RH). | <u>(T-20, "f</u> over. Re | Removal and Installation". efer to DLK-228, "FRONT | FENI | DER DRIP COVER : Removal and |
| umper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. 1. Remove front fender drip constallation". 2. Remove bumper molding to RH). | <u>(T-20, "f</u> over. Re | Removal and Installation". efer to DLK-228, "FRONT | FENI | DER DRIP COVER : Removal and |
| umper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. 1. Remove front fender drip constallation". 2. Remove bumper molding to RH). | <u>(T-20, "f</u> over. Re | Removal and Installation". efer to DLK-228, "FRONT | FENI | DER DRIP COVER : Removal and |
| umper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. 1. Remove front fender drip contract installation". 2. Remove bumper molding under the result of the result of | <u>(T-20, "f</u> over. Re upper fi | Removal and Installation". efer to <u>DLK-228, "FRONT</u> xing screws (A) (LH and | FENI | DER DRIP COVER : Removal and |
| Bumper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. Remove front fender drip control in the stallation. Remove bumper molding to RH). | <u>(T-20, "f</u> over. Re upper fi | Removal and Installation". efer to <u>DLK-228, "FRONT</u> xing screws (A) (LH and | FENI | DER DRIP COVER : Removal and |
| a. Fully open hood assembly. a. Fully open hood assembly. b. Remove front grille. Refer to EX. c. Remove bumper molding. 1. Remove front fender drip contract installation". 2. Remove bumper molding under RH). | <u>(T-20, "f</u> over. Re upper fi | Removal and Installation". efer to <u>DLK-228, "FRONT</u> xing screws (A) (LH and | FENI | DER DRIP COVER : Removal and |
| Bumper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX. Remove bumper molding. Remove front fender drip contract installation". Remove bumper molding under the result of the | <u>(T-20, "f</u> over. Re upper fi | Removal and Installation". efer to <u>DLK-228, "FRONT</u> xing screws (A) (LH and | FENI | DER DRIP COVER : Removal and |
| Bumper fascia is made of resin. No. Fully open hood assembly. Remove front grille. Refer to EX Remove bumper molding. Remove front fender drip contract in the second s | <u>(T-20, "f</u> over. Re upper fi | Removal and Installation". efer to <u>DLK-228, "FRONT</u> xing screws (A) (LH and | FENI | DER DRIP COVER : Removal and |

JMKIA5427ZZ


(A)

< REMOVAL AND INSTALLATION >


- 4. Pull bumper molding (1) toward the direction shown in the figure, and then disengage bumper molding fixing metal clips (LH and RH).
 - : Metal clip




- 5. Remove bumper molding.
- 4. Remove front over fender front side. Refer to EXT-27, "Removal and Installation".
- 5. Remove clips of bumper upper side.
- 6. Remove bumper fascia assembly fixing screws (A) (LH and RH).



∠___ : Pawl





8. Disconnect corner sensor harness connector and fog lamp harness connector.

Remove bumper fascia assembly. CAUTION:

When removing bumper fascia assembly, 2 workers are required so as to prevent it from dropping.

- 10. Remove the following parts after removing bumper fascia assembly.
 - Front grille lower molding.
 - Front bumper grille.
 - Front fog lamp assembly (LH and RH). Refer to EXL-158, "Removal and Installation" .
 - Front fog lamp finishers (LH and RH)
 - Bumper side bracket (LH and RH)
 - License plate bracket
- 11. Remove bumper upper retainer.

INSTALLATION

Note the following item, and then install in the reverse order of removal.

Install License Plate Bracket According To The Following Procedures


CAUTION:

Situate the vehicle on a flat and solid surface.

EXT-14

< REMOVAL AND INSTALLATION >

1. Open positioning holes (2) [φ 8.0 mm (0.315 in)] on bumper fascia (1) based on small dimples (3) as shown in the figure.




| Dimension | | | | |
|--|----------------------|--|--|--|
| A: Distance from small dimple | : 20.5 mm (0.807 in) | | | |
| B: Distance from small dimple : 54.0 mm (2.126 in) | | | | |

- 2. Install J nuts to license plate bracket.
- Insert locate pins (4) of license plate bracket (3) into positioning holes (2) of bumper fascia (1).

Align license plate bracket installation holes to the small dimple positions, and then fix license plate bracket using double-sided tape [t: 1.2 mm (0.047 in)].

Always replace double-sided tape with a new one, if license plate bracket reused.



А

В

D

Ε

F


Н

J

4. Tighten mounting screws to install license plate bracket.

NOTE:

- The following table shows the specified values for checking normal installation status.
- Fitting adjustment cannot be performed.



| Portion | | Clearance | Surface height difference |
|------------------------------------|-------|------------------------------------|---------------------------|
| Front grille – | A – A | 3.7 – 8.3 mm | (-0.9) – (+3.9) mm |
| Hood | | (0.146 – 0.327 in) | [(-0.035) – (+0.154) in] |
| Bumper fascia assembly – | В – В | 0.1 – 3.4 mm | (-1.9) – (+1.9) mm |
| Front bumper molding | | (0.004 – 0.134 in) | [(-0.075) – (+0.075) in] |
| Front bumper molding – Headlamp | C – C | 0.1 – 2.5 mm (0.004 – 0.098 in) | _ |
| Front bumper molding – | D – D | 1.2 – 5.8 mm | (-2.4) – (+2.4) mm |
| Hood | | (0.047 – 0.228 in) | [(-0.094) – (+0.094)] |

Revision: 2014 October

< REMOVAL AND INSTALLATION >

| Portion | | Clearance | Surface height difference | |
|-----------------------------------|-------|------------------------------------|---------------------------|--|
| Front bumper molding– Headlamp | E-E | 0.1 – 2.5 mm (0.004 – 0.098 in) | _ | |
| Bumper fascia assembly – | F – F | 0.2 – 3.1 mm | 0.5 – 3.5 mm | |
| Headlamp | | (0.008 – 0.122 in) | (0.020 – 0.138 in) | |
| Front fender – | G – G | 0.0 – 0.7 mm | (-1.0) – (+1.0) mm | |
| Front bumper molding | | (0.000 – 0.028 in) | [(-0.039) – (+0.039) in] | |
| Front fender – | H – H | 0.0 – 0.8 mm | (-0.7) – (+1.3) mm | |
| Bumper fascia assembly | | (0.000 – 0.031 in) | [(-0.028) – (+0.051) in] | |

REAR BUMPER

Exploded View

INFOID:000000010257788

А

В

С

D

Ε

F

G

Н


J

L

Μ

Ν

Ο



- 1.
- 4. Bumper side stay LH
- 7. Grommet

- 5. Grommet
- 8. Reflex reflector LH
- 6. Bumper fascia assembly

 - 9. Bumper stay LH

REAR BUMPER

< REMOVAL AND INSTALLATION >

- 10. Bumper lower finisher
- 13. Bumper side stay RH
- 16. Bumper stay RH
- Reflex reflector RH
 Energy absorber

17. Bumper side bracket RH

- 12. Bumper stay RH
- 15. Bumper side reinforcement RH

INFOID:000000010257789

 \bullet , \blacktriangle , \blacksquare , \bullet : Indicates that the part is connected at points with same symbol in actual vehicle.


Removal and Installation

REMOVAL


CAUTION:


Bumper fascia is made of resin. Never apply strong force to it, and be careful to prevent contact with oil.

- 1. Fully open back door assembly.
- 2. Remove rear combination lamp (LH and RH). Refer to EXL-166, "Removal and Installation".
- 3. Remove bumper fascia fixing clips (A) and screws (B) (LH and RH).



- 4. Remove rear over fender fixing screws.
- 5. Remove bumper fascia lower mounting bolts.
- 6. Remove screws (A) of bumper fascia front end upper (LH and RH).





- 7. Pull bumper fascia assembly toward the vehicle outside as shown by the arrow in the figure, and then disengage the bumper fascia assembly from bumper side brackets (LH and RH).
 - کے : Pawl
- 8. Remove bumper fascia assembly. CAUTION:

When removing bumper fascia assembly, 2 workers are required so as to prevent it from dropping.

- 9. Remove the following parts after removing rear bumper fascia.
 - Bumper side brackets (LH and RH)
 - Reflex reflector (LH and RH)
 - Bumper stay bracket (LH and RH)

REAR BUMPER

< REMOVAL AND INSTALLATION >


- Bumper stay (LH and RH)
- Bumper protector (LH and RH)
- Bumper side reinforcement (LH and RH)

10. Remove energy absorber.

INSTALLATION

Note the following item, and then install in the reverse order of removal.

- NOTE:
- The following table shows the specified values for checking normal installation status.
- Fitting adjustment cannot be performed.



| Portion | | Clearance | Surface height difference | - |
|---|-------|------------------------------------|--|---|
| Bumper fascia assembly – Rear fender | A – A | 0.0 – 1.0 mm (0.000 – 0.039 in) | (-0.7) – (+1.3) mm [(-0.028) – (+0.051) in] | - |
| Bumper fascia assembly – Rear combination lamp | B – B | 0.3 – 3.0 mm (0.012 – 0.118 in) | _ | - |
| Bumper fascia assembly – Back door | C – C | 2.8 – 6.1 mm (0.110 – 0.240 in) | _ | _ |
| Bumper fascia assembly – Back door | D – D | 3.8 – 7.8 mm (0.150 – 0.307 in) | _ | - |

EXT

L

Μ

Ν

Ο

Ρ

А


В

FRONT GRILLE

< REMOVAL AND INSTALLATION > FRONT GRILLE

Exploded View

INFOID:000000010257790



1. Front grille


2. Front emblem


<u>^</u>: Pawl


Removal and Installation

REMOVAL

- 1. Fully open hood assembly.
- 2. Apply protective tape (A) on surrounding area of front grille (1).








FRONT GRILLE

< REMOVAL AND INSTALLATION >

4. Pull front grille toward the direction shown in the figure, and then disengage front grille fixing clips.



- 5. Disconnect front camera harness connector, and then remove front grille.
- 6. Remove emblem after removing front grille.

INSTALLATION

Install in the reverse order of removal.



EXT

L

Μ

Ν

Ο

Ρ

Ε

F


G

Н

COWL TOP

Exploded View

INFOID:000000010257792



- 1. Front fender cover RH
- 4. Cowl top cover

- EPT seal [t: 15.0 mm (0.591 in)]
 Front fender cover LH
- 3. Cowl top cover seal
- 6. Double-sided tape
 - [t: 1.2 mm (0.047 in)]


- 7. EPT seal [t: 3.0 mm (0.118 in)]
- : Always replace after every disassembly.
- () : Clip
- <u></u>
 へ
 : Pawl

Removal and Installation

REMOVAL

- 1. Fully open hood assembly.
- 2. Remove front wiper arm (LH and RH). Refer to WW-65, "Removal and Installation".
- 3. Remove front fender cover (LH and RH).
- 4. Disconnect front washer tube connector.
- 5. Remove cowl top cover fixing clips.
- 6. Pull forward to release cowl top cover (1) from windshield glass. CAUTION:

When performing the procedure after removing cowl top cover, cover the lower end of windshield glass with urethane etc.



- 7. Remove the following parts after removing cowl top cover.
 - Cowl top seal
 - Washer nozzle (LH and RH)

COWL TOP

< REMOVAL AND INSTALLATION >

| Washer tube EPT sealer | А |
|--|---|
| INSTALLATION Note the following items and then, install in the reverse order of removal. CAUTION: • When installing cowl top cover, check that blind clips are securely fitted in panel holes on body, and | В |
| then press them in. Always replace cowl top cover EPT sealer with a new one when installing old cowl top cover. After installing, perform adjustment of wiper arms. Refer to <u>WW-65, "Adjustment"</u>. | С |
| | D |
| | Е |

I

F

G

Н

J

EXT

L

Μ

Ν


Ο

FENDER PROTECTOR FENDER PROTECTOR

FENDER PROTECTOR : Exploded View

INFOID:000000010257794

FENDER PROTECTOR



- 1. Fender protector
- 2. U nut

3. Over fender

- 4. Fender
- 5. Hoodledge insulator
- 6. Fender clip

A: To hoodledge panel

 \bullet , \blacktriangle : Indicates that the part is connected at points with same symbol in actual vehicle.

FENDER PROTECTOR : Removal and Installation

INFOID:000000010257795

REMOVAL

- 1. Remove mounting bolts, from front lower.
- 2. Release front fender protector fixing clips, and then remove front fender protector.
- 3. Disengage hoodledge insulator fixing pawls, and then remove hoodledge insulator.

INSTALLATION


Install in the reverse order of removal. REAR WHEEL HOUSE PROTECTOR

FENDER PROTECTOR

< REMOVAL AND INSTALLATION >

REAR WHEEL HOUSE PROTECTOR : Exploded View

INFOID:000000010257796




FLOOR SIDE FAIRING

< REMOVAL AND INSTALLATION >

FLOOR SIDE FAIRING

Exploded View

INFOID:000000010257798



1. Front under cover

2. Front under deflector

Removal and Installation

INFOID:000000010257799

REMOVAL

Front Under Cover

- 1. Remove front under deflector mounting bolts, and then remove front under deflector.
- 2. Remove front under cover mounting bolts, and then remove front under cover.

INSTALLATION


Install in the reverse order of removal.

OVER FENDER

Exploded View

INFOID:000000010257800

А



Revision: 2014 October


OVER FENDER

< REMOVAL AND INSTALLATION >

 Disengage front over fender rear side fixing pawls from behind of front fender, and the pull front over fender front side toward the direction shown in the figure.



CAUTION: Never pull the front over fender strongly.




- 4. Remove front fender protector. Refer to EXT-24, "FENDER PROTECTOR : Removal and Installation"
- 5. Remove side step front side fixing clips.
- 6. Disengage front over fender rear side fixing pawls from behind of fender, and then pull front over fender front side toward the direction shown in the figure.



CAUTION:

Never pull the front over fender strongly.




7. Remove front over fender.

Rear over fender

- 1. Remove rear over fender rear side fixing screws and bolts.
- 2. Remove rear fender protector rear side. Keep the service area. Refer to <u>EXT-25</u>, "REAR WHEEL HOUSE <u>PROTECTOR</u> : Removal and Installation".
- 3. Disengage rear over fender rear side fixing pawls from behind of rear fender, and the pull rear over fender rear side toward the direction shown in the figure.

کے : Pawl




- 4. Remove rear fender protector. Refer to <u>EXT-25</u>, "REAR WHEEL HOUSE PROTECTOR : Removal and <u>Installation</u>".
- 5. Remove rear over fender front side fixing screws and bolts.
- 6. Using a remover tool (A), disengage the clips from the rear over fender by starting from the rear.

(]) :Clip

CAUTION:

- Apply a protective tape (B) on the body to protect the painted surface from damage.
- Disengage the clips slowly and carefully.
- Never pull the front over fender strongly.



| < REMOVAL AND | > INSTALLATION > |
|---------------|------------------|
|---------------|------------------|

INSTALLATION

Install in the reverse order of removal.

CAUTION:

- When installing, check visually the over fender and the clips, then replace them with new parts if they have been damaged.
- When installing over fender, check that blind clips are securely fitted in panel holes on body, and then press them in.

J

EXT

L

Μ

Ν

Ο

Ρ

А

В

С

D

Е

F

G


Н

ROOF RAIL

Exploded View

INFOID:000000010257802

INFOID:000000010257803




- 1. 4.
 - Center leg cover
- 5. Rear roof rail cover

2 : Pawl

Removal and Installation


REMOVAL

- 1. Remove front roof rail cover (1) with remover tool (A). **CAUTION:** Apply protective tape (B) around the roof rail.
 - ♪ : Pawl



2. Remove center roof rail cover (1) with flat-bladed screwdriver (A).


八:Pawl



ROOF RAIL


< REMOVAL AND INSTALLATION >

- Remove rear roof rail cover (1) with remover tool (A).
 CAUTION: Apply protective tape (B) around the roof rail.
 - 2 : Pawl



- 4. Remove roof rail mounting bolts, and then remove roof rail assembly.
- 5. Pull to the side, disengage pawls and remove center leg cover (1).





6. Remove roof rail center leg assembly mounting bolt, and then remove roof rail center leg assembly.

INSTALLATION

Install in the reverse order of removal.

J

EXT

L

Μ

Ν

Ο

Ρ

А

В

С

D

Ε


F

Н

ROOF SIDE MOLDING

Exploded View

INFOID:000000010257804



- Roof side molding cap 1.
- Roof side molding 2. Grommet

5.

Grommet 3.

(へ): Pawl

4.

Removal and Installation


Roof side molding clip

REMOVAL

- 1. Remove roof rail assembly and roof rail center leg assembly. Refer to EXT-30, "Removal and Installation".
- Disengage roof side molding (1) fixing clips with remover tool 2. (A), and then remove roof side molding. **CAUTION:**

Apply protective tape (B) around the roof side molding.

() : Clip



INSTALLATION

Note the following item, and then install in the reverse order of removal.

CAUTION:

To install roof side molding, check if all clips are matched over holes of panel on vehicle, then push it.

DOOR OUTSIDE MOLDING


< REMOVAL AND INSTALLATION >

DOOR OUTSIDE MOLDING

Exploded View

INFOID:000000010257806

А



Removal and Installation

FRONT DOOR OUTSIDE MOLDING

Removal


1. Fully open door window.

INFOID:000000010257807

DOOR OUTSIDE MOLDING


< REMOVAL AND INSTALLATION >

- Twist and pull up to upper side, and then remove front door outside molding (1).
 CAUTION:
 - Apply protective tape around front door panel.
 - Never twist and pull up to door outside molding strongly.



REAR DOOR OUTSIDE MOLDING

- 1. Fully open door window.
- Twist and pull up to upper side, and then remove rear door outside molding (1).
 CAUTION:
 - Apply protective tape around rear door panel.
 - Never twist and pull up to door outside molding strongly.



Installation Install in the reverse order of removal.

DOOR PARTING SEAL


< REMOVAL AND INSTALLATION >

DOOR PARTING SEAL

Exploded View

INFOID:000000010257808

А



- 1. Fully open door.
- Disengage the door parting seal fixing clips with a remover tool, and then remove door parting seal.
 CAUTION:
 - Disengage the clips slowly and carefully.
 - Never pull the door parting seal strongly.

INSTALLATION

Note the following items, and then install in the reverse order of removal. **CAUTION:**

EXT-35


- When installing, check visually the clips, then replace them with new parts if they have been damaged.
- When installing door parting seal, check that blind clips are securely fitted in panel holes on body, and then press them in.
- Always replace double-sided tape with a new one, if door parting seal.

SILL MOLDING

Exploded View

INFOID:000000010257810

А



INSTALLATION

Note the following items, and then install in the reverse order of removal.

CAUTION:


- When installing, check visually the sill molding and the clips, then replace them with new parts if they have been damaged.
- When installing the sill molding, check that blind clips are securely fitted in panel holes on body, and then press them in.

Ν

DOOR SASH COVER

Exploded View

INFOID:000000010257812



Removal and Installation

FRONT DOOR SASH COVER


Removal

1. Remove front door sash cover fixing clips.

DOOR SASH COVER

< REMOVAL AND INSTALLATION >

- Insert a remover tool (A) between front door sash cover (1) and door panel, cut double-sided tape using a cutter (B) while lifting front door sash cover, and remove front door sash cover.
 CAUTION:
 - Use a remover tool which is made of a material that does not damage door panel.
 - Never lift front door sash cover with excessive force.



 $\widehat{\mathbf{2}}$

Installation

Note the following items, and then install in the reverse order of removal. **CAUTION:**


• When installing, slide and install front door sash cover (2) from door rear side, so that front door outside molding (1) is not deformed.

- Replace double-sided tape on back of front door sash cover with a new double-sided adhesive tape if front door sash cover is reused.
- Replace EPT sealer of front door sash cover with a new EPT sealer if front door sash cover is reused.
- Remove double-sided adhesive tape remaining on body and back of front door sash cover using double-sided adhesive tape remover when removing front door sash molding.
- Install after cleaning adhesive parts of door side and back of front door sash cover.
- To secure contact, do not wash vehicle within 24 hours after installation.

REAR DOOR SASH COVER

Removal

- 1. Remove rear door sash cover fixing clips.
- Insert a remover tool (A) between rear door sash cover (1) and door panel, cut double-sided tape using a cutter (B) while lifting rear door sash cover, and remove rear door sash cover.
 CAUTION:
 - Never use an item as a remover tool that could damage door panel.
 - Never lift rear door sash cover with excessive force.



Installation Note the following items, and install in the reverse order of removal. CAUTION: EXT

Ε

F


Н

JMKIA5005ZZ

DOOR SASH COVER

< REMOVAL AND INSTALLATION >

• When installing, slide and install rear door sash cover (2) from door front, so that rear door outside molding (1) is not deformed.



- Replace double-sided adhesive tape on back of rear door sash cover with a new double-sided adhesive tape if rear door sash cover is reused.
- Replace EPT sealer of rear door sash cover with a new EPT sealer if rear door sash cover is reused.
- Remove double-sided adhesive tape remaining on body and back of rear door sash cover using double-sided adhesive tape remover when removing rear door sash cover.
- Install after cleaning adhesive parts of door side and back of rear door sash cover.
- To secure contact, do not wash vehicle within 24 hours after installation.

FRONT PILLAR FINISHER


< REMOVAL AND INSTALLATION >

FRONT PILLAR FINISHER

Exploded View

INFOID:0000000010257814


А



REAR SPOILER

Exploded View

INFOID:000000010257816



- 1. Rear spoiler assembly
- 2. Grommet
- 4. High-mounted stop lamp cover

[t: 1.6 mm (0.063 in)]

- 7. Double-sided tape
- 5. Washer nozzle

8. EPT sealer [t: 4.0 mm (0.157 in)]

- 3. High-mounted stop lamp
- 6. EPT sealer [t: 5.0 mm (0.197 in)]

- Always replace after every disassembly.
- () : Clip


Removal and Installation

REMOVAL

- 1. Remove back door trim. Refer to INT-39, "Removal and Installation".
- 2. Remove rear spoiler mounting nuts.
- 3. Cut rear spoiler fixing double-sided tape with cutter knife.
- Disengage rear spoiler fixing clips with remover tool (A), and then remove rear spoiler.
 CAUTION:

Apply a protective tape (B) on body panel and rear spoiler to protect the painted surface from damage.

(_) : Clip



REAR SPOILER

< REMOVAL AND INSTALLATION >

| 5. Remove following parts after removing rear spoiler. High-mounted stop lamp Grommets Washer nozzle | A |
|---|---|
| INSTALLATION Note the following items, and then install in the reverse order of removal. CAUTION: | В |
| Be careful no to damage the back door. Always replace double-sided tape with a new one, if rear spoiler is reused. Remove double-sided tape remaining on back door panel and back of rear spoiler with a double-sided tape removing rear spoiler. | С |
| When installing, visually check the rear spoiler and the clips, then replace them with new parts if they are damaged. | D |
| When installing rear spoiler, check that clips and bolts are securely fitted in back door panel holes, and then press them in. Never wash the vehicle within 24 hours after installing so as to keep adhesive. | |
| | F |
| | |

Н

G

J

EXT

L

M

Ν


0

DRIP MOLDING

Exploded View

INFOID:000000010257818

INFOID:000000010257819



- 1. Drip molding clip
- 2. Drip molding

Removal and Installation

REMOVAL

Remove drip molding fixing clips from rear end to front end using remover tool (A).

CAUTION:

Apply protective tape (B) on body panel to protect the painted damage from damage.

() : Clip

INSTALLATION

Note the following items, and then install in the reverse order of removal. **CAUTION:**


When installing, check visually the drip molding and clips, then replace them with new parts if they are damaged.

BACK DOOR FINISHER

Exploded View

INFOID:000000010257820

А



License lamp

Back Door Finisher Center Lower

- 1. Remove back door trim. Refer to INT-39, "Removal and Installation".
- 2. Remove back door finisher center lower mounting nuts.
- 3. Disengage fixing clips, and then remove back door finisher center lower.


INSTALLATION

Install in the reverse order of removal.

SIDE STEP

Exploded View

INFOID:000000010257822



- 1. Side step bracket 2. Side step
- \bullet , \blacktriangle , \blacksquare : Indicates that the part is connected at points with same symbol in actual vehicle.

Removal and Installation

INFOID:000000010257823

REMOVAL

- 1. Remove side step mounting bolts, and then remove side step.
- 2. Remove side step bracket mounting bolts, and then remove side step brackets.

INSTALLATION

Install in the reverse order of removal.